



KEYED DEMOLITION NOTES

- 1 REMOVE & DISPOSE OF OR REUSE THE CONCRETE GROP / PAVE & PIPE PILE & MASONRY WALLS
- 2 ALUMINUM WINDOW SHALL BE SALVAGED AND DELIVERED TO STORAGE LOCATION TO BE DESIGNATED BY OWNER
- 3 REMOVE & DISPOSE A JOIST PORTION OF WOOD GIRDERS FROM TRIM TO EXPOSE THE ROOF OF EXISTING FOUNDATION WALL
- 4 REFER TO MECHANICAL BUILDING DEMOLITION DRAWINGS FOR OTHER ITEMS OF SELECTIVE DEMOLITION

GENERAL NOTES

1. MASONRY DEMOLITIONS SHOWN ARE NOMINAL. SITE PERSONS SHALL VERIFY TO PROVIDE NECESSARY DIMENSIONS FOR CORRECT DEMOLITION. MASONRY SHALL BE DEMOLISHED TO THE FINISH SURFACE OF THE EXISTING CONCRETE FOUNDATION.
2. FOUNDATION DESIGN IS BASED ON THE ASSUMPTION THAT THE EXISTING FOUNDATION WAS INSTALLED AS A GROUND FLOOR SLAB ON GRADE. NO GROUND IMPROVEMENT IS ASSUMED. IF EVIDENCE OF GROUND IMPROVEMENT IS OBSERVED, THE ASSUMPTIONS OF THE FOUNDATION CONTRACTOR SHALL CONTROL THE ARCHITECT OR ENGINEER.

FINISH NOTES

1. INTERIOR & EXTERIOR SURFACES OF CONCRETE BLOCK MASONRY ARE NOT SCHEDULED FOR FINISH FINISHES.
2. EXTERIOR SURFACES TO BE PAINTED. WOOD & FINISHED FLOORING (INCLUDING FLOORING) TO BE PAINTED WITH A PROTECTIVE FINISH.
3. INTERIOR SURFACES TO BE PAINTED. INCLUDE FINISH CEILING, WOOD TRIM & WOOD FLOORS TO BE PAINTED WITH A PROTECTIVE FINISH.
4. FINISH SURFACES TO BE PAINTED. INCLUDE FINISH CEILING, WOOD TRIM & WOOD FLOORS TO BE PAINTED WITH A PROTECTIVE FINISH.

DOOR SCHEDULE

ORIG. ID	DOOR	UNIT	FRAME	THRESH.
D1	2'0" x 7'0" WOOD	1	WOOD	WOOD
D2	2'0" x 7'0" WOOD	1	WOOD	WOOD

A.O.T. DISTRICT NO. 4 OFFICE HEATING SYSTEM REPLACEMENT WHITE RIVER JUNCTION VERMONT
MECHANICAL BUILDING ADDITION DEMOLITION, FOUNDATION & FLOOR PLANS, ELEVATIONS, SECTIONS & DETAILS

MCKNIGHT ASSOCIATES, Architects, P.C.
WINDBROOK, Skylark Terrace - Barre, Vermont 05641
LANE ASSOCIATES, CONSULTING ENGINEERS, P.C.
51 KILLINGTON AVENUE RUTLAND, VERMONT 05701

