# QUANTITY SHEET

**STATE OF VERMONT**
**AGENCY OF TRANSPORTATION**

APPROXIMATE SUMMARY OF QUANTITIES

| QUANTITIES GRAND TOTAL | UNIT | ITEMS | ITEM NO. | |
|---|---|---|---|---|
| 1000 | CY | COMMON EXCAVATION | 203.15 | |
| 230 | CY | EXCAVATION OF SURFACES AND PAVEMENTS | 203.28 | |
| 200 | CY | EARTH BORROW | 203.30 | |
| 4900 | SY | FINE GRADING-SUBGRADE | 203.40 | |
| 550 | CY | SUBBASE OF CRUSHED GRAVEL (FINE GRADED) | 301.26 | |
| 8 | CWT | EMULSIFIED ASPHALT | 404.65 | |
| 870 | TON | BITUMINOUS CONCRETE PAVEMENT (PG 58-28) | 406.25 | |
| 30 | CY | CONCRETE, CLASS B | 501.25 | |
| 1400 | LB | REINFORCING STEEL | 507.15 | |
| 10 | GAL | WATER REPELLENT | 514.10 | |
| 1 | HR | ALL PURPOSE EXCAVATOR RENTAL, TYPE I (NOT A BID ITEM) | 608.25 | |
| 1 | HR | TRUCK RENTAL (NOT A BID ITEM) | 608.37 | |
| 12 | MGAL | DUST CONTROL WITH WATER | 609.10 | |
| 10 | CY | STONE FILL, TYPE I | 613.10 | |
| 1 | LS | TESTING EQUIPMENT - CONCRETE | 631.16 | |
| 1 | LS | TESTING EQUIPMENT - BITUMINOUS | 631.17 | |
| 1 | LS | MOBILIZATION | 635.10 | |
| 30 | SY | GEOTEXTILE UNDER STONE FILL | 649.31 | |
| 290 | SY | GEOTEXTILE FOR SILT FENCE | 649.51 | |
| 50 | LB | SEED | 651.15 | |
| 300 | LB | FERTILIZER | 651.18 | |
| 2 | TON | AGRICULTURAL LIMESTONE | 651.20 | |
| 2 | TON | HAY MULCH | 651.25 | |
| 100 | EA | HAY BALES FOR EROSION CONTROL | 651.26 | |
| 170 | CY | TOPSOIL | 651.35 | |
| 150 | SY | EROSION MATTING | 654.10 | |
| 1 | LS | ROADSIDE REST FACILITY (MOD.) (2 SALT/SAND SHEDS 40' x 84') | 658.15 | |
| | | DECIDUOUS TREES | | |
| | | (ACER RUBRUM) RED SWAMP MAPLE (2/2.5" CAL.) | 656.30 | * |
| | | (QUERCUS RUBRA) RED OAK (2/2.5" CAL) | 656.30 | * |

*ITEM OUT OF ORDER

DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

| STATIONS FROM | STATIONS TO | PAVEMENT WIDTHS | | | EQUATIONS + | EQUATIONS - | FEET | MILES | REMARKS |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |
| TOTALS | | | | | | | | | |

DATE PLOTTED: 12 FEB 1999

PROJECT NAME MIDDLEBURY SALT SHED
PROJECT NUMBER STP SALT(9)



FEB 12 1999