QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.
2000	CY	COMMON EXCAVATION	203.15
30	CY	SOLID ROCK EXCAVATION	203.16
1050	CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28
5200	SY	FINE GRADING-SUBGRADE	203.40
1000	CY	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.26
8	CWT	EMULSIFIED ASPHALT	404.65
950	TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.25
9	CY	CONCRETE, CLASS B	501.25
325	LB	REINFORCING STEEL	507.15
2	GAL	WATER REPELLENT	514.10
1	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I (NOT A BID ITEM)	608.25
1	HR	TRUCK RENTAL (NOT A BID ITEM)	608.37
11	MGAL	DUST CONTROL WITH WATER	609.10
5	CY	STONE FILL, TYPE I	613.10
8	CY	STONE FILL, TYPE II	613.11
1	LS	TESTING EQUIPMENT - CONCRETE	631.16
1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17
1	LS	MOBILIZATION	635.10
30	SY	GEOTEXTILE UNDER STONE FILL	649.31
450	SY	GEOTEXTILE FOR SILT FENCE	649.51
70	LB	SEED	651.15
10	LB	SEED - WINTER RYE	651.17
400	LB	FERTILIZER	651.18
2	TON	AGRICULTURAL LIMESTONE	651.20
2	TON	HAY MULCH	651.25
100	EA	HAY BALES FOR EROSION CONTROL	651.26
400	CY	TOPSOIL	651.35
200	SY	EROSION MATTING	654.10
1	LS	ROADSIDE REST FACILITY (MOD.) (2 SALT/SAND SHEDS 40' x 84')	658.15

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

DATE PLOTTED: 10 SEP 1999

PROJECT NAME NEW HAVEN SALT SHED
PROJECT NUMBER STP SALT (12)