QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION
STRUCTURES DIVISION

ITEM NO.	ITEM	UNIT	QUANTITY BREAKDOWN								TOTAL	FINAL
203.28	EXCAVATION OF SURFACES AND PAVEMENT	CY								250	250	
203.30	EARTH BORROW	CY								400	400	
203.40	FINE GRADING - SUBGRADE	SY								9600	9600	
301.26	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	CY								150	150	
404.65	EMULSIFIED ASPHALT	CWT								14	14	
406.25	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	TON								1700	1700	
608.25	ALL PURPOSE EXCAVATOR RENTAL, TYPE I (NABI)	HR								1	1	
608.37	TRUCK RENTAL (NABI)	HR								1	1	
609.10	DUST CONTROL WITH WATER	MGAL								6	6	
635.10	MOBILIZATION	LS								1	1	
649.51	GEOTEXTILE FOR SILT FENCE	SY								150	150	
651.15	SEED	LB								25	25	
651.17	SEED-WINTER RYE	LB								10	10	
651.18	FERTILIZER	LB								125	125	
651.20	AGRICULTURAL LIMESTONE	TON								1	1	
651.25	HAY MULCH	TON								1	1	
651.26	HAY BALES FOR EROSION CONTROL	EACH								25	25	
651.35	TOPSOIL	CY								70	70	
658.15	ROADSIDE REST FACILITY (MOD) (2 SHEDS 40' x 84')	LS								1	1	

ITEM NO.	ITEM	UNIT	QUANTITY BREAKDOWN							TOTAL	FINAL

BRIDGE AT STATION
LOCATION

PREPARED BY: B. Donald
CHECKED BY: G. Newbury
SUPERVISOR:

PROJECT: WILLIAMSTOWN
PROJECT NO: STP SALT (5)S
BR OF
SHEET NO: 5 OF 5