



- GENERAL NOTES**
1. CONCRETE - 3000 PSI, 28 DAYS, MAXIMUM SLUMP 4"
  2. ALL EXPOSED CONCRETE TO BE RUBBED AND CURED.
  3. ALL EXPOSED SLABS & CONCRETE STEPS DURATION OF JOB, UNTIL ACCESSIBILITY.
  4. EXPOSED CURB CORNERS TO BE CHAMFERED 1/4"
  5. ALL SLAB SHOWING TO BE IN PLACE MIN (3) DAYS @ 70°F. RE-SHORE AFTER STRIPPING.
  6. PLASTER, MASONRY FROM CONCRETE - ALL RE-STEEL TO BE LAPPED 40 DIA.
  7. REINFORCING STEEL TO BE LAPPED ON SLAB BOLTS & HI-CHAIRS, LESS TO BE PVC PLASTIC.
  8. ALL REINFORCING STEEL TO BE LAPPED 40 DIA.
  9. ALL REINFORCING STEEL TO BE LAPPED 40 DIA.
  10. ONE SECTION OF RAILING, EACH SIDE OF STAIRS TO BE REMOVABLE.
  11. PIPE RAILING POSTS TO BE LEDDED INTO STEELS.
  12. ALL CONCRETE SLABS SHALL BE 18" COMPACTED THROUGHOUT.
  13. ALL CONCRETE SHALL BE PLACED IN 18" MAXIMUM LIFTS.

NO.	BY	DATE	REVISION
1	TJS	8/21/75	REVISION 3 - CURB DETAILS

STATE OF VERMONT  
DIVISION OF STATE BUILDINGS  
AGENCY OF ADMINISTRATION  
MONTPELIER, VERMONT

Standard Highway Garage Building  
DETAILS OF MEZZANINE, BOILER  
ROOM SLABS AND CONC. STAIRWAY

SCALE: As noted

DESIGNED BY: [Signature]  
DRAWN BY: [Signature]  
DATE: 10/18/74  
APPROVED BY: [Signature]

DATE: 10/18/74  
DWG. NO. A4  
REVISION: 4 of 4