

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION
STRUCTURES DIVISION

ITEM NO.	ITEM	UNIT	QUANTITY BREAKDOWN				TOTAL	FINAL	ITEM NO.	ITEM	UNIT	QUANTITY BREAKDOWN				TOTAL	FINAL
203.28	EXCAVATION OF SURFACES AND PAVEMENT	CY				80	80										
203.40	FINE GRADING - SUBGRADE	SY				900	900										
301.26	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	CY				90	90										
404.65	EMULSIFIED ASPHALT	CWT				5	5										
406.25	BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	TON				420	420										
608.25	ALL PURPOSE EXCAVATOR RENT, TYPE 1 (NAB1)	HR				1	1										
608.37	TRUCK RENTAL (NAB1)	HR				1	1										
635.10	MOBILIZATION	LS				1	1										
649.51	GEOTEXTILE FOR SILT FENCE	SY				100	100										
651.15	SEED	LB				25	25										
651.17	SEED - WINTER RYE	LB				10	10										
651.18	FERTILIZER	LB				150	150										
651.20	AGRICULTURAL LIMESTONE	TON				1	1										
651.25	HAY MULCH	TON				1	1										
651.26	HAY BALES FOR EROSION CONTROL	EACH				60	60										
651.35	TOPSOIL	CY				80	80										
658.15	ROADSIDE REST FACILITY (PDD) L.S. (SALT SHED 40 X 64')	L.S.				1	1										
658.15	ROADSIDE REST FACILITY (PDD) L.S. (SALT SHED 50 X 64')	L.S.				1	1										

BRIDGE AT STATION _____ LOCATION _____

PREPARED BY: B. Donald SUPERVISOR

CHECKED BY: G. Newbury

PROJECT: CANAAN BR _____ OF _____

PROJECT NO: 5TP SALT(3)5 SHEET NO: 6 OF 6