



FINISH SCHEDULE		WALLS		CEILING		DOORS		WINDOWS		
FLOOR	FLOOR FINISH	BASE	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH
BASEMENT	CONCRETE - EPOXY PAINT	NONE	CONCRETE	EPOXY PAINT	CONCRETE	EPOXY PAINT	HOLLOW METAL - PRIMED	-	WOOD - VINYL CLAD	-
FIRST FLOOR INTERIOR	CONCRETE - EPOXY PAINT	150 mm VINYL COVE BASE	CONCRETE BLOCK	EPOXY PAINT	SHEETROCK & TRIM	EPOXY PAINT	HOLLOW METAL - PRIMED	-	VINYL CLAD TRIM - CEDAR	EPOXY PAINT BLEACHING OIL
EXTERIOR	-	-	CEDAR	BLEACHING OIL	-	-	-	-	-	-

RECORD DRAWING

SHOWN PICTORALLY
MAY NOT BE TO SCALE

THESE AS-BUILT OR RECORD DRAWINGS HAVE BEEN PREPARED, IN PART, ON THE BASIS OF INFORMATION COMPILED AND FURNISHED BY OTHERS. THE ENGINEER WILL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH HAVE BEEN INCORPORATED INTO THIS DOCUMENT AS A RESULT OF INFORMATION BY OTHERS.

5	9/30/98	NO AS-BUILT INFORMATION ADDED	DSM	KAS	TIMOTHY D. SMITH & ASSOCIATES, PC ARCHITECTS
4	12/29/96	CONTRACT PLANS	DSM	MPY	OLD RAILROAD STATION
3	11/11/96	FINAL REVIEW REVISIONS	DSM	MPY	NORTH BENNINGTON, VERMONT 05257
2	6/4/96	REVISIONS PER REVIEW COMMENTS	DSM	MPY	FAX 802-442-5244
1	4/8/96	REVISIONS PER REVIEW COMMENTS	DSM	MPY	WRIGHT ENGINEERING, LTD. CIVIL ENGINEERS
NO.	DATE	REVISIONS	DRWN	CHKD	128 MERCHANTS ROW - P.O. BOX 176 RUTLAND, VERMONT 05702-0176 FAX 802-775-2511



PROJECT NO. IM 091-1 (29)
WATER & SEWER EXTENSION PROJECT
TOWN OF GUILDFORD
TOWN OF BRATTLEBORO

DESIGN BY: MPY
DRAWN BY: DSM
CHECKED BY: MPY

STATE OF VERMONT
AGENCY OF TRANSPORTATION
SOUTHEAST VERMONT WELCOME CENTER
GUILDFORD, VERMONT

DATE: 1-2-96
SHEET NO. 25 OF 55 SHEETS

