QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.			UTILITY	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						10*	CY	MUCK EXCAVATION	203.20	
						70	CY	SAND BORROW	203.31	
						4050	CY	TRENCH EXCAVATION OF EARTH	204.20	
						200	CY	GRANNULAR BACK FILL FOR STRUCTURES	204.30	
						200	CY	SUBBASE OF GRAVEL	301.15	
						5*	CY	CONCRETE, CLASS C	501.30	
						16	EACH	PRC MANHOLES WITH C.I. COVER	604.20	
						30	LF	REMOVING AND RESETTING FENCE	620.50	
						205	LF	8" D.I. SEWER PIPE W/MECHANICAL JOINTS	628.28	
						1	LS	TRANSFER TO NEW SYSTEM-SANITARY SEWER	628.42	
						3705	LF	8" PVC SEWER PIPE	628.35	
						1	LS	MOBILIZATION	635.10	
						205	LF	JACKING OR BORING 20" WELDED STEEL PIPE	643.20	
						60*	LB	SEED	651.15	
						500*	LB	FERTILIZER	651.18	
						2*	TON	HAY MULCH	651.25	
						250*	CY	TOPSOIL	651.35	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

* INDETERMINATE QUANTITY

STATIONS		PAVEMENT WIDTHS			EQUATIONS		FEET	MILES	REMARKS
FROM	TO				+	-			
TOTALS									

PROJECT NAME WILLISTON REST AREAS
PROJECT NUMBER IR089-2(13)

SHEET 2 OF 8 SHEETS

D-1 JAN 85

BRUNING 65083

D&K DWG NO. 7035