QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
1	1	EA	DEMOLITION AND DISPOSAL OF BUILDING	202.10	EST.
10	10	CY	SOLID ROCK EXCAVATION	203.16	-
30	30	CY	EXCAVATION OF SURFACES AND PAVEMENT	203.28	EST.
2	2	EA	SANITARY SEWER MANHOLES (MODIFIED)	604.24	-
100	100	LF	REMOVING AND RESETTING CURB	616.40	-
195	195	SY	BRICK PAVING	618.20	3
15	15	SY	BRICK PAVING (MODIFIED-GRASS PAVERS)	618.20	4
80	80	LF	REMOVAL OF EXISTING FENCE	620.55	-
1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
1	1	EA	UTILITY VAULT (MODIFIED)	636.20	-
100	100	LF	TEMPORARY 4'' WHITE LINE (TAPE TYPE II)	646.60	EST.
100	100	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.82	EST.
40	40	LB	SEED	651.15	EST.
250	250	LB	FERTILIZER	651.18	EST.
1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
1	1	TON	HAY MULCH	651.25	EST.
5	5	CY	TOPSOIL	651.35	EST.
22	22	EA	DECIDUOUS TREES (ACER SACCHARUM) SUGAR MAPLE, 5'' CAL. B&B	656.30	-
32	32	EA	DECIDUOUS TREES (MALUS BACCATA) SIBERIAN CRAB, 3 1/2'' CAL. B&B	656.30	-
220	220	EA	PERENNIALS (HEMEROCALLIS SP.) DAYLILLY 1 GALLON	656.40	-
4	4	EA	TRANSPLANTING TREES	656.45	-
1	1	LS	ROADSIDE REST FACILITY (BUILDING)	658.15	-
2	2	EA	REST AREA BENCH	658.20	-
22.25	22.25	SF	TRAFFIC SIGNS, TYPE A	675.20	-
344	344	SF	TRAFFIC SIGNS, TYPE B	675.21	-
5.5	5.5	SF	TRAFFIC SIGNS, TYPE B (MODIFIED)	675.21	MOD.
107.2	107.2	LB	FLANGED CHANNEL SIGN POST	675.30	-
1779	1779	LB	W-SHAPED STEEL SIGN POST	675.31	-
167.2	167.2	LB	TUBULAR STEEL SIGN POST	675.33	-
6	6	EA	FOUNDATION FOR W-SHAPE STEEL POST 24'' DIAMETER	675.41	-
2	2	EA	FOUNDATION FOR TUBULAR STEEL POST	675.43	-
9	9	EA	REMOVING SIGNS	675.50	-
1	1	EA	ERECTING SALVAGED SIGNS	675.60	-
3	3	EA	LIGHT POLE (MODIFIED)	679.45	MOD.
1	1	EA	TRAVEL INFORMATION MAP PLAZA, TYPE A	680.30	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

19-APR-1994
/const/infoctr/infoctr.dgn

PROJECT NAME BRADFORD NB REST AREA
PROJECT NUMBER IM BLDG(1)

SHEET 2 OF 24 SHEETS