GENERAL SITEWORK NOTES

1. THE CONTRACTOR SHALL REPAIR ALL EXISTING ROAD/WALK PAVEMENT AND FOUNDATIONS WHERE DAMAGED OR DISTURBED BY THE WORK OF THIS CONTRACT AT NO COST TO THE OWNER. REPAIRS SHALL BE MADE WITH MATERIALS OF EQUAL QUALITY AND TO THE EXISTING PAVEMENT/ FOUNDATION DEPTH. THE AREA OF REPAIR SHALL BE SQUARE CUT AND NOT LESS THAN 10'x10'(OR WIDTH OF WALK) UNLESS APPROVED BY THE OWNER.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEMOLITION, REMOVAL AND DISPOSAL OF ALL EXISTING VEGETATION, PAVEMENT, CONCRETE ITEMS AND STRUCTURES NECESSARY TO PERFORM THE WORK.
3. THE CONTRACTOR SHALL REPAIR ALL EXISTING LAWN OR VEGETATED AREAS DAMAGED OR DISTURBED DURING WORK OF THIS CONTRACT. REPAIRS SHALL BE MADE WITH LIKE PLANT MATERIAL IN ACCORDANCE WITH METHODS AND MATERIALS APPROVED BY THE OWNER.
4. AT THE COMPLETION OF THE GRADING, ALL SLOPES, DITCHES, AND ALL DISTURBED AREAS SHALL BE HAND RAKED, SMOOTH AND FREE OF POCKETS, WITH SUFFICIENT SLOPE TO ENSURE DRAINAGE.
5. FINISH SLOPES, DITCHES AND DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 4 INCHES OF TOPSOIL MIX, AND BE FERTILIZED, SEEDED, LIMED, AND MULCHED. TURF ESTABLISHMENT SHALL BE PERFORMED PER SECTION 651 OF THE VERMONT HIGHWAY DEPT. SPECS.
6. ALL FILL SHALL BE PLACED IN 6 INCH LIFTS AND THOROUGHLY COMPACTED TO 95% OF MAXIMUM DENSITY OF OPTIMUM MOISTURE CONTENT AS DETERMINED BY ASTM D968 STANDARD PROCTOR, UNLESS NOTED OTHERWISE.
7. HEALTHY EXISTING TREES ON SITE NOT SCHEDULED FOR REMOVAL OR RE-LOCATION SHALL BE MARKED AND PROTECTED FROM DAMAGE DURING THE WORK.
8. FINISH GRADE, TOPSOIL AND SEED ALL DISTURBED AREAS NOT DESIGNATED FOR ANOTHER MATERIAL.
9. ADJUST ALL EXISTING MANHOLES, CATCH BASINS, RIMS, COVERS, VALVES AND OTHER SITE STRUCTURES AND UTILITIES WHERE ENCOUNTERED TO MEET NEW LINE AND GRADE OF FINISHED LAWN AND PAVEMENT.
10. ALL EXISTING PAVEMENT MARKINGS SHALL BE OBSCURED PRIOR TO PAINTING OF NEW MARKINGS. SEE SPECS FOR INSTALLATION OF NEW MARKINGS.
11. ALL HIGHWAY AND OTHER SIGNAGE NOT SHOWN IN THESE DRAWINGS WILL BE PROVIDED BY THE OWNER. THE CONTRACTOR SHALL NOTIFY AND COORDINATE THE SCHEDULING OF THESE ITEMS WITH THE OWNER.
12. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL TRASH AND DEBRIS GENERATED DURING THE WORK FROM THE SITE AT THE END OF THE PROJECT.

EROSION CONTROL NOTES

1. FOLLOW VT-AOT GUIDELINES FOR EROSION AND SEDIMENT CONTROL FOR ALL PHASES OF DEMOLITION, SITE PREPARATION AND CONSTRUCTION.
2. THE TOPSOIL SHALL BE REMOVED FROM THE AREAS TO BE GRADED AND STOCKPILED. STAKED HAY BALES OR A SILT FENCE SHALL BE PLACED CONTINUOUSLY AROUND THE BOTTOM OF THE PILE. NOTE THAT AT ALL SILT FENCES, FABRIC SHALL BE KEYED INTO GROUND 6" MIN.
3. ALL DISTURBED AREAS SHALL HAVE A SILT FENCE TO CONTROL SEDIMENTATION INCLUDING STAKED HAY BALES WHERE REQUIRED.
4. PROVIDE STAKED HAY BALES AND FILTER FABRIC AT ALL AFFECTED STORM DRAIN INLETS.
5. ALL TEMPORARY EROSION CONTROL FACILITIES SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR.
6. ALL EROSION CONTROL FACILITIES SHALL BE PROMPTLY INSPECTED AND REPAIRED AFTER EACH HEAVY RAINFALL.
7. KEEP WORK AREA TO A MINIMUM BY STRIPPING ONLY THOSE AREAS THAT WILL BE WORKED ON IMMEDIATELY.
8. REMOVE NO MORE VEGETATIVE COVER THAN IS NECESSARY TO GRADE THE SITE AS SHOWN ON THE PLANS.

GENERAL PROJECT NOTES

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS RELATED TO THE EXISTING BUILDING AND SITE. NEW WORK SHALL BE LAID OUT AND DIMENSIONS CHECKED FOR CONFORMITY WITH DRAWINGS. ADVISE OWNER AND A/E OF ANY DISCREPANCIES IMMEDIATELY.
2. THE EXISTING ROOF IS ASSUMED TO BE DESIGNED FOR 40+ LBS/SF LIVE LOAD AND TO BE CAPABLE OF SUPPORTING THE PROPOSED ROOF OVERBUILD. THE CONTRACTOR SHALL NOTIFY THE A/E WHEN THE ROOF SYSTEM AND BEARING POINTS AT STONE FACADE HAVE BEEN UNCOVERED TO ALLOW REVIEW OF HIDDEN EXISTING STRUCTURAL CONDITIONS.
3. STONEWORK: LIMITED STONE REMOVAL AND INFILL IS REQUIRED TO THE MAIN FACADE. THE CONTRACTOR SHALL ATTEMPT TO SALVAGE REMOVED STONE FOR REUSE AT INFILL LOCATIONS. IF ADDITIONAL STONE IS REQUIRED, NEW TO MATCH EXISTING IN SIZE, COLOR, TEXTURE, ETC., SHALL BE SUBMITTED TO THE A/E FOR APPROVAL. MORTAR SHALL MATCH EXISTING IN COMPOSITION, JOINT SIZE AND SHAPE AND COLOR. ALL STONEWORK SHALL BE CLEANED WITH LOW PRESSURE WATER WASH.
4. DRAINAGE OF PAVERS/WALKS: PITCH ALL SUBBASE AND BASE COURSE MATERIALS SIMILAR TO THE FINISHED SURFACES. PONDING WITHIN THE BASE AND SUBBASE COURSES WILL NOT BE ACCEPTABLE. ALL WALKS AND PAVERS SHALL PITCH TO AVOID STANDING WATER.
5. ALL EXTERIOR AND INTERIOR SURFACES SHALL RECEIVE AT LEAST ONE COAT OF PAINT, OR AS SCHEDULED ON THE ROOM FINISH SCHEDULE.
6. THE CONTRACTOR SHALL COORDINATE AND PROVIDE ALL, CUTOUTS, BLOCKING, BACKPLATES, RECESSED SLABS REQUIRED TO INSTALL THE WORK AND EQUIPMENT SHOWN.
7. THE CONTRACTOR SHALL PROVIDE ALL TRENCHES FOR MECHANICAL WORK INCLUDING BACKFILL, SLAB REPAIR, AND RESURFACING/REFINISHING TO MATCH EXISTING ADJACENT OR AS REQUIRED TO RECEIVE SCHEDULED NEW FINISHES.
8. CONCRETE INFILLS IN SLAB CUTS/OPENINGS OVER 6" WIDE SHALL BE DOWELED INTO EXISTING CONCRETE SLAB WITH #4 BARS DRILLED AND DRIVEN (6" TYP.) AT 2'-0" O.C. MAX.

REFINISHING OF EXISTING SURFACES

1. WHERE EXISTING SURFACES ARE SCHEDULED TO REMAIN, THEY SHALL BE PREPARED AS CALLED FOR IN THE PAINTING SPECIFICATION AND REFINISHED PER THE ROOM FINISH SCHEDULE.
2. WHERE EXISTING SURFACES ARE DAMAGED OR LEFT UNFINISHED BY REMOVALS OR NEW CONSTRUCTION, REPAIR OR REPLACE DAMAGED AREAS TO MATCH EXISTING ADJACENT MATERIAL AND SURFACES, INCLUDING TEXTURE, LEVEL, ALIGNMENT, COLOR AND APPEARANCE. ALL PATCHES SHALL BE BLENDED INTO ADJACENT SURFACES.

1/00 GENERAL NOTES — N.T.S.

EARTH
STONE, GRAVEL
BITUMINOUS PAVING
CONCRETE
PRE-CAST CONCRETE
CONCRETE MASONRY UNITS
BRICK
STONE
SAND, MORTAR
ALUMINUM
STEEL
SHEET METAL
REINFORCING – W.W.F.
REINFORCING BAR (RODS)
PLASTER/LATH
GYPSUM WALLBOARD
GLASS
PLYWOOD
WOOD (FINISHED)
WOOD BLOCKING (CONT.) (NOM. DIMEN.)
WOOD SHIMS (NON-CONT.)
BATT INSULATION
RIGID INSULATION
ACOUSTIC TILE
PARTICLE BOARD
PLASTIC LAMINATE (ON PLYWD)
CARPET
QUARRY TILE
VAPOR BARRIER

JOB SPECIFIC LEGEND

CONCRETE
PRECAST CONCRETE BRICK PAVERS
ASPHALT
FULLY PAINTED AREA
501 EXISTING 1' CONTOUR LINE
500 EXISTING 5' CONTOUR LINE
NEW 1' CONTOUR LINE
SIGNAGE
EXISTING TREE TO REMAIN
EXISTING PINE TREE TO REMAIN
TREE TO BE RELOCATED
NEW OR RELOCATED TREE OR SHRUB
EXISTING SHRUB TO REMAIN
EXISTING STREET LIGHT TO REMAIN
NEW LUMINAIRE
FLAGPOLE

2/00 MATERIALS LEGEND — NO SCALE

ROOM FINISH SCHEDULE

RM #	RM NAME	FLOOR MAT.	FLOOR COLOR	BASE MAT.	BASE COLOR	WALLS MAT.	WALLS FIN.	WALLS COLOR	CEILING MAT.	CEILING FIN.	CEILING COLOR	WDW TRIM MAT.	WDW TRIM FIN.	WDW TRIM COLOR	REMARKS
01	VESTIBULE	F.G.	-	*	PT-1	*	*	PT-1	WD	O	PT-2	*	*	PT-1	*STOREFRONT GLAZING SYSTEM (see spec's)
02	LOBBY	EPOX/S	EP-1	EPOX/S	EP-1	E/GWB	G	PT-3	E/GWB	F-1	PT-3	WD	O	PT-2	
03	WOMEN TLT	EPOX/S	EP-1	EPOX/S	EP-1	EXG.	*G	*PT-3	EXG.	F-1	PT-3	WD	L	PT-5	*only at areas covered by GWB
04	MEN TLT	EPOX/S	EP-1	EPOX/S	EP-1	EXG.	*G	*PT-3	EXG.	F-1	PT-3	WD	L	PT-5	*only at areas covered by GWB
05	UNISEX TLT	EPOX.	EP-1	BPT.	ST-1	SQFT.	ST-1/ST-2		GWB	F-1	PT-3	-	-	-	
06	CORRIDOR	EPOX.	EP-1	EPOX.	EP-1	GWB	G	PT-3	GWB	F-1	PT-3	-	-	-	
07	UTIL. CORR.	EXG.	-	-	-	-	-	-	-	-	-	-	-	-	
08	CLOSET	EPOX.	EP-1	EPOX.	EP-1	GWB	G	PT-3	NO CEILING		-	-	-	-	PATCH TO MATCH

NOTE

1. NEW WOOD AT EXTERIOR SOFFITS AND VESTIBULE CEILING SHALL BE CEDAR AND HAVE PT-6
2. EXG. WOOD AT EXTERIOR SOFFITS SHALL HAVE PT-6
3. WOOD AT DOUBLE HUNG WINDOW AND FOLDING TABLE SHALL BE MAPLE AND HAVE FINISH "O"
4. THE STOREFRONT SYSTEM INCLUDING THE ALUMINUM DOORS SHALL BE PT-1
5. ALL INTERIOR HM DOORS SHALL BE PT-4 EXCEPT DOORS #111, #114 WHICH SHALL HAVE PT-3
6. ALL INTERIOR HM FRAMES SHALL BE PT-5 EXCEPT DOORS #111, #114 WHICH SHALL HAVE PT-3
7. ALL EXTERIOR HM DOORS AND FRAMES SHALL BE PT-5
8. ALL EXTERIOR WINDOW TRIM SHALL BE PT-5
9. SEE ADDITIONAL FINISHES IN SPEC'S FINISHES (0, F-1, G, L) CAN BE LOCATED IN SECTION 09900, 3.04- INTERIOR SURFACES

ALL MFR'S LISTED ARE SPECIFIED FOR DESIGN, QUALITY AND FINISH. OTHER APPROVED EQUIVALENT WILL BE ACCEPTABLE.

PAINT

PT-1 KYNAR 500 FINISH IN IVY GREEN
PT-2 CLEAR WOOD FINISH (see type "o" in spec's)
PT-3 P&L #1285 SKY CLOUD
PT-4 P&L #1341 ITALIAN BLUE
PT-5 P&L #1513 SPECTRUM GREEN
PT-6 P&L STAINSHIELD #3-107 OIL

FLOORING

EP-1 SIKAKL COMBINATION OF FLAKES USING: #19 STEEL BLUE, #18 SKY BLUE, and #20 SEAFOAM GREEN

Degadur 4125L Installed by Epoxy Systems Jericho Vt.

STRUCTURAL GLAZED FACING TILES

ST-1 STARK # 123 DUNE BLUSH
ST-2 STARK #121 CANYON CLAY (ACCENT)

ST-1 Stark # 681 Nimbus White
ST-2 Stark # 195 Caribbean Reef (Accent)

	RM #	MATERIAL / FINISHES
EXTERIOR	FLOOR	PRECAST CONCRETE BRICK PAVERS HANOVER "APPIAN" COLOR: NATURAL/ CHARCOAL BLEND
	STONE WALL	EXISTING GRANITE
	WALL	WOOD SHAKES COLOR: PRATT & LAMBERTS SOLID COLOR STAIN HARBOR FOG
	COLUMN	STEEL, COLOR: PRATT & LAMBERT # 1513 SPECTRUM GREEN
	STOREFRONT	INCL. DOOR, COLOR: KYNAR 500, IVY
	DOORS	HM, COLOR: PRATT & LAMBERT # 1513 SPECTRUM GREEN
	DOORFRAMES	HM, COLOR: PRATT & LAMBERT # 1513 SPECTRUM GREEN
	WINDOWFRAME	WOOD, COLOR: PRATT & LAMBERT # 1513 SPECTRUM GREEN
	SOFFIT	NEW & EXIST.WOOD, P & L STAINSHIELD #3-107 OIL
	FASCIA	WOOD, COLOR: PRATT & LAMBERT # 1513 SPECTRUM GREEN
	ROOF	SHINGLES, COLOR: (BIRD) CHESTNUT BROWN
INTERIOR	FLOORS: 02,03,04 05,06,08	EPOXY/ MASTIC FLOORING COLORS: ~~STEEL BLUE, SKY BLUE, SEAFOAM GREEN~~
	07	PAINTED CONCRETE FLOOR, COLOR: PATCH TO MATCH EXISTING
	WALLS: STONE WALL	EXISTING GRANITE
	01	STOREFRONT SYSTEM SERIES 3000, COLOR KYNAR 500, IVY
	02,03,04 06,08	NEW AND EXISTING GWB, COLOR: PRATT & LAMBERT #1285 SKY CLOUD
	05	STARK STRUCTURAL TILES, COLOR: ~~#123 DUNE BLUSH~~ #681 Nimbus White
	05	STARK STRUCTURAL TILES, ACCENT COLOR ~~#121 CANYON CLAY~~ #195 Caribbean Reef
	DOORS: 02,03,04 05,06,08	DOOR #:103,104,106,107,108 HM, COLOR: PRATT & LAMBERT # 1341 ITALIAN BLUE
	DOORFRAMES: 02,03,04 05,06,08	DOOR #:103,104,106,107,108 HM, COLOR: PRATT & LAMBERT # 1531 SPECTRUM GREEN
	ACCESS DOORS & FRAMES: 03,06	DOOR #111 & 114, COLOR: P & L #1285 SKY CLOUD
	WINDOWFRAMES: 02,03,04 05,06,08	WOOD, COLOR: PRATT & LAMBERT # 1513 SPECTRUM GREEN AND CLEAR FINISH
	CEILINGS: 02,03,04 05,06,	NEW AND EXISTING GWB, COLOR: # 1285 SKY CLOUD
	01	T & G WOOD SIDING, COLOR: P & L STAINSHIELD #3-107 OIL

SEEDING FORMULA
URBAN AREAS

% WT.	LBS./A.	NAME	PUR %	GERM %
42.5	34.0	CREEPING RED FESCUE	98	85
10.0	8.0	PERENNIAL RYE GRASS	95	90
42.5	34.0	KENTUCKY BLUE GRASS	85	85
5.0	4.0	ANNUAL RYE GRASS	95	85
100.00	80.0			

THE SEED MIXTURE SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS WEED SEED.
SEED- TO BE APPLIED PER SEEDING FORMULA DIRECTED BY THE ENGINEER.
FERTILIZER- FORMULA 10-20-10 TO BE USED WITH SEED, APPLIED AT THE RATE OF 500 LBS./ACRE (HYDROSEEDERS MAY USE 19-19-19 FORMULA)
AGRICULTURAL LIMESTONE- TO BE APPLIED AT THE RATE OF 2 TONS/ACRE OR AS DIRECTED BY THE ENGINEER.
HAY MULCH- TO BE PLACED ON EARTH SLOPES AT THE RATE OF 2 TONS/ACRE, OR AS DIRECTED BY THE ENGINEER.
TOPSOIL- TO BE USED WITH SEED AS INDICATED ON THE PLANS, OR AS DIRECTED BY THE ENGINEER.

●	AT	DIMEN.	DIMENSION
∠	ANGLE	DL	DEAD LOAD
℄	CENTERLINE	DN.	DOWN
[	CHANNEL	DTL.	DETAIL
⊥	PERPENDICULAR	DWG.	DRAWING
▭	PLATE	E.J.	EXPANSION JOINT
⌀	ROUND/DIAMETER	E.P.	ELECTRIC PANEL
		EIFS	EXTERIOR INSUL. & FINISH SYSTEM
		E.W.C.	ELECTRIC WATER COOLER
A.F.F.	ABOVE FINISH FLOOR	EA.	EACH
A.P.	ACCESS PANEL	EL.	ELEVATION
A.T.	ASPHALT TILE	ELEC.	ELECTRIC(AL)
A/C	AIR CONDITIONING	ELEV.	ELEVATOR
AC.	ACRE	ENTR.	ENTRANCE
ACT.	ACOUSTICAL TILE	EQ.	EQUAL
ADD'N.	ADDITION	EQUIP.	EQUIPMENT
ADD.	ADDENDUM	ESTIM.	ESTIMATE
ADJUST.	ADJUSTABLE	EXG.	EXISTING
ALT.	ALTERNATE	EXH.	EXHAUST
ALUM.	ALUMINUM	EXP.	EXPOSED
ANCH.	ANCHOR(AGE)	EXPAN.	EXPANSION
ANOD.	ANODIZED	EXT.	EXTERIOR
APPROX.	APPROXIMATE	F.B.O.	FURNISHED BY OTHER
ARCH.	ARCHITECT(URAL)	F.C.U.	FAN COIL UNIT
ASB.	ASBESTOS	F.D.	FLOOR DRAIN
ASPH.	ASPHALT	F.E.	FIRE EXTINGUISHER
		F.E.C.	FIRE EXTINGUISHER CABINET
B.M.	BENCHMARK	F.H.	FIRE HYDRANT
B.U.R.	BUILT-UP ROOF	F.N.D.	FEMININE NAPKIN DISPOSAL
B.W.	BOTH WAYS	F.O.	FRAME OPENING
B/O	BOTTOM OF	F.P.	FIREPROOFING
BD.	BOARD	F/O	FACE OF
BLDG.	BUILDING	F/R	FIRE-RESISTIVE
BLKG.	BLOCKING	FAP	FIRE ANNUNCIATION (ALARM) PANEL
BLKT.	BLANKET	FDN.	FOUNDATION
BM.	BEAM	FIN.	FINISH(ED)
BRG.	BEARING	FIXT.	FIXTURE
BRK.	BRICK	FL'G.	FLASHING
BSMT.	BASEMENT	FL.	FLOOR
BVL.	BEVELED	FM	FACTORY MUTUAL
		FNV.	FEMININE NAPKIN VENDOR
C.H.	CHEMICAL HARDENER	FR.	FRAME
C.I.	CAST IRON	FRM'G.	FRAMING
C.I.P.	CAST-IN-PLACE	FT.	FOOT/FEET
C.J.	CONTROL JOINT	FTG.	FOOTING
C.L.L.	CONTRACT LIMIT LINE	FUR.	FURRING
C.M.P.	CORRUGATED METAL PIPE	FURN.	FURNISHED/FURNITURE
C.M.T.	CERAMIC MOSAIC TILE	FWC	FABRIC WALL COVERING
C.M.U.	CONCRETE MASONRY UNIT		
C.T.	CERAMIC TILE	G.B.	GRAB BAR
CABT.	CABINET	G.C.	GENERAL CONTRACTOR
CARP.	CARPENTER	G.C.T.	GLAZED CERAMIC TILE
CB.	CHALKBOARD	GA.	GAUGE
CEM.	CEMENT	GALV.	GALVANIZED
CL.	CLOSET	GKT.	GASKET
CLG.	CEILING	GL.	GLASS, GLAZING
CLR.	CLEAR	GWB.	GYPSUM WALLBOARD
COL.	COLUMN	GYP.	GYPSUM
COMB.	COMBINATION	H.	HEIGHT
COMP.	COMPOSITE	H.C.	HOLLOW CORE
CONC.	CONCRETE	H.M.	HOLLOW METAL
CONST.	CONSTRUCTION	H/C	HANDICAPPED
CONT.	CONTINUOUS	HBD.	HARDBOARD
CONTR.	CONTRACTOR	HDWD.	HARDWOOD
CORR.	CORRIDOR	HDWR.	HARDWARE
CORRUG.	CORRUGATED	HGLR.	HEAT/GLARE/LIGHT REDUCING(GLASS)
CPT.	CARPET	HORIZ.	HORIZONTAL
CRS.	COURSE(S)	HR.	HOUR
C.U.H.	CABINET UNIT HEATER	HVAC.	HEATING/VENTILATING/AIR COND.
D.	DEPTH	I.C.S.	INSULATED COMPOSITE SIDING
D.F.	DRINKING FOUNTAIN	I.D.	INSIDE DIAMETER
D.H.	DOUBLE HUNG	IMPREG.	IMPREGNATED
D.O.	DOOR OPENING/DITTO	INCL.	INCLUDE(D) (-ING)
DEFL.	DEFLECTION	INSUL.	INSULATE(D) (-ION) (-ING)
DIA.	DIAMETER	INT.	INTERIOR
DIAG.	DIAGONAL	INV.	INVERT
		JAN.	JANITOR
		JT.	JOINT
		L.	LENGTH
		LAM.	LAMINATE(D)
		LAV.	LAVATORY
		LF	LINEAR FEET
		LG.	LONG
		LL	LIVE LOAD
		LLH.	LONG LEG HORIZONTAL
		LLV.	LONG LEG VERTICAL
		LOC.	LOCATE(D) (-ION)
		LT-GA.	LIGHT GAUGE
		LTG.	LIGHTING
		LTL.	LINTEL
		LVR.	LOUVER
		M.O.	MASONRY OPENING
		M.R.	MOISTURE RESISTANT
		MACH.	MACHINE
		MAT.	MATERIAL
		MAX.	MAXIMUM
		MECH.	MECHANICAL
		MET.	METAL(LIC)
		MEZZ.	MEZZANINE
		MFR.	MANUFACTURER
		MIN.	MINIMUN
		MISC.	MISCELLANEOUS
		MLDG.	MOULDING
		MMB.	MEMBRANE
		MSRY.	MASONRY
		MTL.	METAL
		MULL.	MULLION
		N.A.	NOT APPLICABLE
		N.I.C.	NOT IN CONTRACT
		N.S.	NON-SLIP
		N.T.S.	NOT TO SCALE
		NAT.	NATURAL
		NO.	NUMBER
		NOM.	NOMINAL
		O.A.	OVERALL
		O.C.	ON CENTER
		O.D.	OUTSIDE DIAMETER
		OPNG.	OPENING
		OPP.	OPPOSITE
		OPPH.	OPPOSITE HAND
		OSU	OHIO STATE UNIV. (TEST)
		PAF	POWER ACTIVATED FASTENER
		P.M.S.	PREFORMED METAL SIDING
		P.V.C.	POLYVINYL CHLORIDE
		PBD.	PARTICLE BOARD
		PERIM.	PERIMETER
		PL.	PLASTIC/PLATE
		PLAM.	PLASTIC LAMINATE
		PLAS.	PLASTER
		PLBG.	PLUMBING
		PLYWD.	PLYWOOD
		PNL.	PANEL
		PREFAB.	PREFABRICATE(D)
		P.T.	PEESSURE TREATED
		PT./PTD.	PAINT/PAINTED
		PTN.	PARTITION
		PVMT.	PAVEMENT
		Q.T.	QUARRY TILE
		QTY.	QUANTITY
		R.	RADIUS/RISER
		R.B.	RUBBER BASE
		R.D.	ROOF DRAIN
		R.F.	RUBBER FLOORING
		R.O.	ROUGH OPENING
		REF.	REFERENCE
		REINF.	REINFORCED
		REQ'D	REQUIRED
		RET.	RETURN
		REV.	REVISED/REVISION
		RM.	ROOM
		RUB.	RUBBER
		S.C.	SOLID CORE
		S.S.	STAINLESS STEEL
		S.T.C.	SOUND TRANSMISSION CLASS
		SCH.	SCHEDULE
		SECT.	SECTION
		SH.	SHEET
		SHTH.	SHEATHING
		SIM.	SIMILAR
		SLNT.	SEALANT
		SLR.	SEALER
		SPEC.	SPECIFICATION
		SPR.	SPRINKLER
		SQ.	SQUARE
		ST./STL.	STEEL
		STD.	STANDARD
		STR./STRUCT.	STRUCTURE(-AL)
		SUSP.	SUSPENDED
		SYM.	SYMMETRICAL
		T.	TRANSFORMER/TREAD
		T.&G.	TONGUE & GROOVE
		T/CONC.	TOP OF CONCRETE
		T/D	TOP OF DECK
		T/O	TOP OF
		T/S	TOP OF STEEL
		T/W	TOP OF WALL
		TB	TACKBOARD
		TEL.	TELEPHONE
		TEM.	TEMPERED
		TEMP.	TEMPERATURE
		TERM.	TERMINAL
		TERRAZ.	TERRAZZO
		TH.	THICK(NESS)
		THRES.	THRESHOLD
		TLT.	TOILET
		TRANS.	TRANSPORT
		TRANSF.	TRANSFORMER
		TRANSP.	TRANSPARENT
		TRS.	TILE REDUCER STRIP
		TYP.	TYPICAL
		U.C.	UNDERCUT
		U.N.O.	UNLESS NOTED OTHERWISE
		UL	UNDERWRITER'S LAB. (TEST)
		UR.	URINAL
		V.	VINYL
		V.B.	VAPOR BARRIER
		V.I.F.	VERIFY IN FIELD
		V.P.	VISION PANEL
		VAR.	VARNISH
		VB	VINYL BASE
		VCT.	VINYL COMPOSITION TILE
		VERT.	VERTICAL
		VEST.	VESTIBULE
		VNR.	VENEER
		VT	VINYL TILE
		VWC.	VINYL WALLCOVERING
		W.	WIDTH
		W.C.	WATER CLOSET
		W.GL.	WIRE GLASS
		W.P.	WATERPROOF/WORKPOINT
		W.R.	WATER REPELLENT/RESISTANT
		W.S.	WEATHER STRIP
		W.W.	WINDOW WALL
		W.W.F.	WELDED WIRE FABRIC
		W/	WITH
		W/O	WITHOUT
		WDW.	WINDOW

JOB SPECIFIC ABBREVIATIONS

EPOX.	FULL LAYER OF EPOXY/ MASTIC FLOORING
EPOX./S	SKIMCOAT LAYER OF EPOXY/ MASTIC FLOORING
F.G.	FLOOR GRATE
SQFT	STRUCTURAL GLAZED FACING TILE

3/00 ABBREVIATIONS — NO SCALE

DATUM POINT: T/CONC. T/STL. T/SUBSTRATE
STRUCTURAL GRID LINE
DOT: DIMENSION TO ℄ OR TO STRUCTURAL GRID LINE
SLASH: DIMENSION TO ACTUAL FACE OF MATERIAL; ACTUAL WALL THICKNESS
GRIDLINES
FINISHED SURFACE LINES – CUT
ELEMENTS BELOW CUT LINE – HIDDEN
ELEMENTS ABOVE CUT LINE – DASHED SOFFIT ABOVE CO-ORDINATE W/ CEILING PLANS, SECTIONS, DETAILS.
ACCESSORY ITEM: SEE ACCESSORY SCHEDULE FOR DESCRIPTION.
SPECIAL NOTATION (e.g. DEMO NOTE)
LOUVER TYPE DESIGNATION
DOOR DESIGNATION
PARTITION TYPE: SEE PARTITION LEGEND ON A-0.
ROOM NUMBER DESIGNATION: SEE FINISH SCHEDULE.

SECTION OR DETAIL REFERENCE: DETAIL NUMBER; SHEET NUMBER WHERE DETAIL IS LOCATED.
VIEW DIRECTION
SIM. OPPH.
SPECIAL NOTES
WALL SECTIONS; THRU-BUILDING SECTIONS
ROOM / WALL ELEVATIONS
REVISION NOTE
DETAIL No.
DETAIL TITLE
SCALE
SHEET No.

JOB SPECIFIC
EXISTING SURFACES
FINISHED SURFACE LINES – NEW
EXISTING DOOR TO REMAIN: SEE DOOR SCHEDULE INFORMATION.
EXISTING DOOR + FRAME TO BE REMOVED: SEE DEMOLITION PLANS.
NEW DOOR WITHIN NEW OR EXISTING CONSTRUCTION: SEE DOOR SCHEDULE INFORMATION.

4/00 SYMBOLS LEGEND — NO SCALE

STATE OF VERMONT
DEPARTMENT OF STATE BUILDINGS
AGENCY OF ADMINISTRATION
MONTPELIER, VERMONT

REST AREA REHABILITATION
LYNDON I-91 SOUTHBOUND
SYMBOLS / LEGEND / NOTES

DATE:	SCALE:	REVISIONS:	DRAWING NO:
JUNE 9, 1995	NO SCALE		00
DRAWN BY: SULI	PROJECT NO: I91-BLDG(2)		SHEET 3 OF 29
APPROVED BY: JBA			