CODE	TIME	BY

GENERAL NOTES:

IMPORTANT

THE INFORMATION LISTED BELOW IS ESSENTIAL AND MUST BE READ CAREFULLY PRIOR TO THE CONSTRUCTION OF YOUR NORTHEASTERN LOG HOME.

ASSEMBLY INSTRUCTION DOCUMENTS:

CONSTRUCTION GUIDE

AN 8-1/2" X 11" PAPERBACK BOOK SENT WITH PRELIMINARY AND FINAL SETS OF PLANS CONTAINING INFORMATION CONCERNING DELIVERY, CONSTRUCTION, AND CARE OF YOUR NORTHEASTERN LOG HOME BUILDING. ALL INDIVIDUALS INVOLVED WITH THIS BUILDING PROJECT SHOULD READ AND UNDERSTAND THIS CONSTRUCTION GUIDE TO ENSURE CORRECT PROCEDURES ARE FOLLOWED. THIS CONSTRUCTION GUIDE SHOULD BE KEPT ON THE JOB SITE FOR REFERENCE WITH THE CONSTRUCTION BLUEPRINTS AT ALL TIMES DURING THE BUILDING PROCESS.

PRELIMINARY PLANS

FULL SETS OF PLANS SENT PRIOR TO THE SHIPMENT OF THE BUILDING. THESE PLANS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES AS THE STAMP ON CEILING FRAMING THRU ELEVATION SHEETS EXPLAINS. IT'S THE CUSTOMER'S RESPONSIBILITY TO FORWARD COPIES TO BOTH THE CONTRACTOR AND BUILDING CODE OFFICIAL. PRELIMINARY PLANS SHOULD BE THOROUGHLY CHECKED BY THE CUSTOMER AND CONTRACTOR IN ORDER TO FAMILIARIZE THEMSELVES WITH OUR BUILDING PROCEDURES AND MATERIALS. IF ANY DISCREPANCIES ARE FOUND WHILE REVIEWING THE PLANS, NOTIFY YOUR SALES REPRESENTATIVE SO THE PROBLEM MAY BE CORRECTED.

(STAMP SHOWN ON PRELIMINARY PLANS)

THESE PLANS CANNOT BE CHANGED
IN TERMS OF APPLICABLE CODES.

HOWEVER, PLANS ARE NOT TO BE
USED FOR BUILDING PURPOSES SINCE
LOG NUMBERING MAY NEED ALTER-
ING AT TIME OF MANUFACTURE.

FINAL PLAN SETS

FULL SETS OF PLANS TO BE USED FOR BUILDING PURPOSES SENT WITH THE DELIVERING CARRIER WHEN THE BUILDING IS TRUCKED TO THE SITE, OR MAILED TO THE OWNER WHEN SITUATIONS DICTATE OTHERWISE. IT IS THE CUSTOMER'S RESPONSIBILITY TO FORWARD ONE COPY OF THE FINAL PLANS AND A COPY OF THE CONSTRUCTION GUIDE TO THE CONTRACTOR. ALL PLANS ARE CAREFULLY CHECKED BEFORE SHIPMENT, HOWEVER, THE POSSIBILITY OF HUMAN ERROR DOES EXIST, THEREFORE, THE CONTRACTOR MUST VERIFY ALL DIMENSIONS SHOWN ON THE PLAN PRIOR TO CONSTRUCTION. ANY DISCREPANCIES SHOULD BE REPORTED TO YOUR SALES REPRESENTATIVE BEFORE ANY CONSTRUCTION BEGINS.

DO NOT SCALE OFF THESE PLANS.

AMPLE DIMENSIONS ARE SHOWN ON THE PLANS TO LOCATE ALL ITEMS. SIMPLE ARITHMETIC MAY BE USED TO DETERMINE THE LOCATION OF THOSE ITEMS NOT DIMENSIONED.

MATERIALS LIST

AN ITEMIZED LIST OF MATERIALS INCLUDED IN YOUR NORTHEASTERN LOG HOME FINAL PLAN SETS, LOCATED IN FRONT OF THE STANDARD DETAIL SHEETS. ALL CODED ITEMS (▷) SHOULD BE INVENTORIED THOROUGHLY ON DELIVERY TO DETERMINE IF ANY DAMAGE HAS RESULTED DURING TRANSIT. NON-CODED ITEMS SHOULD ALSO BE INVENTORIED IF THOSE MATERIALS HAVE BEEN ARRANGED AT THE BUILDING SITE IN AN ORDERLY FASHION TO ENSURE CORRECT IDENTIFICATION AND ACCURATE COUNTING. IF DELIVERED BY TRUCK, ANY DAMAGE SHOULD BE RECORDED ON THE RECEIVING SLIP AND RETURNED WITH THE DRIVER TO INSURE REPLACEMENT OR CREDIT. ONCE THE ITEM ON THE MATERIALS LIST HAS BEEN INVENTORIED, ANY APPARENT SHORTAGES SHOULD BE DOUBLE CHECKED, THEN DISCUSSED WITH YOUR SALES REPRESENTATIVE NO LATER THAN 15 DAYS AFTER DELIVERY. ALSO, PLEASE REMEMBER THAT ONCE THE MATERIALS PACKAGE HAS BEEN DELIVERED, THE RESPONSIBILITY OF THOSE MATERIALS REST SOLELY WITH THE CUSTOMER SO PRECAUTIONS AGAINST PILFERAGE, FIRE, AND VANDALISM SHOULD BE TAKEN. THE CONTRACTOR SHOULD FOLLOW THE MATERIALS LIST CAREFULLY TO DETERMINE PROPER USE OF THE MATERIALS.

STANDARD DETAIL SHEETS

GENERAL DETAILS LABELED SHEETS "A" THROUGH "H" PLACED AT THE END OF THE PLANS. THESE SHEETS MUST BE STUDIED BY THE CONTRACTOR, BEARING IN MIND THEY ARE GENERAL AND THAT SOME DETAILS MAY NOT APPLY TO YOUR BUILDING. SEE "HELPFUL TIPS ON HOW TO READ THESE BLUEPRINTS" ON NEXT SHEET. (SYMBOLS & ABBREVIATIONS)

N.L.H. INC. PLANS ARE DESIGNED BASED ON THESE LUMBER GRADING SPECIFICATIONS:

LOG WALLS: HEADER AND WALL GRADE
EASTERN WHITE PINE OR WESTERN RED CEDAR

DIMENSION LUMBER: (FLOOR FRAMING, PARTITION FRAMING, ETC.)
EASTERN SPRUCE #2 AND BETTER OR EQUIVALENT

PORCH, DECK, AND BALCONY FRAMING:
SOUTHERN YELLOW PINE PRESSURE TREATED #1 OR EQUIVALENT

ALL BEAM STOCK:
EASTERN SPRUCE #2 OR BETTER EXCEPT WHEN NOTED AS #1 ON PLANS

LVL'S (LAMINATED VENEER LUMBER) FROM TECTON LAMINATES CORP.
GRADE: 2.0E SEE BOCA REPORT #88-83
E= $2.0X10^6$ FB=2850

GLULAM: SOUTHERN YELLOW PINE
E= $1.8X10^6$ FB=2400

SAFETY PRECAUTIONS:

SMOKE DETECTOR REQUIREMENTS

SMOKE DETECTORS (SUPPLIED BY OTHERS) SHALL BE INSTALLED AND MAINTAINED IN THE IMMEDIATE VICINTITY OF BEDROOMS, IN ALL BEDROOMS AND IN EACH STORY INCLUDING BASEMENTS. SMOKE DETECTORS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND BE PERMANENTLY WIRED WITHOUT DISCONNECTING SWITCHES. SMOKE DETECTORS TO BE AN APPROVED TYPE IN ACCORDANCE WITH THE BOCA NATIONAL BUILDING CODE. SMOKE DETECTORS TO ALSO BE INSTALLED PER LOCAL BUILDING AND FIRE SAFETY CODE REQUIREMENTS.

LOG AND LOG SIDING WOOD PRESERVATIVE

PRE-CUT LOGS AND LOG SIDING ARE TREATED WITH A WOOD PRESERVATIVE. CARE SHOULD BE USED WHEN HANDLING THIS MATERIAL AS THE PRESERVATIVE COULD CAUSE SKIN AND EYE IRRITATION.

CHANGES TO FINAL PLAN SETS

PLEASE DO NOT MAKE ANY STRUCTURAL CHANGES TO THESE PLANS WITHOUT CONSULTING NORTHEASTERN LOG HOMES, INC.. NORTHEASTERN WILL NOT ASSUME ANY LIABILITY FOR STRUCTURAL DAMAGE RESULTING FROM CHANGES MADE TO THE PLANS OR BY SUBSTITUTION OF MATERIALS DIFFERENT FROM SPECIFICATION ON THE PLANS.

HARDWARE RETIGHTENING REQUIREMENTS

ALL LAG SCREWS AND BOLT CONNECTIONS ON BEAM TRUSSES AND OTHER STRUCTURAL MEMBERS TO BE INSPECTED PERIODICALLY AND RETIGHTENED IF NECESSARY.

INORGANIC ARSENICAL PRESSURE-TREATED WOOD

SOME FRAMING MATERIALS SUPPLIED WITH YOUR NORTHEASTERN LOG HOME PACKAGE SUCH AS 2X6 SILLS, ARE PRESSURE TREATED. EACH PIECE IS CLEARLY MARKED FOR EASY IDENTIFICATION AND IS USUALLY GREENISH IN COLOR.

CONSUMER INFORMATION

THIS WOOD HAS BEEN PRESERVED BY PRESSURE-TREATMENT WITH AN EPA-REGISTERED PESTICIDE CONTAINING INORGANIC ARSENIC TO PROTECT IT FROM INSECT ATTACK AND DECAY. WOOD TREATED WITH INORGANIC ARSENIC SHOULD BE USED ONLY WHERE SUCH PROTECTION IS IMPORTANT. INORGANIC ARSENIC PENETRATES DEEPLY INTO AND REMAINS IN THE PRESSURE-TREATED WOOD FOR A LONG TIME. EXPOSURE TO INORGANIC ARSENIC MAY PRESENT CERTAIN HAZARDS. THEREFORE, THE FOLLOWING PRECAUTIONS SHOULD BE TAKEN BOTH WHEN HANDLING THE TREATED WOOD AND IN DETERMINING WHERE TO USE OR DISPOSE OF THE TREATED WOOD.

USE SITE PRECAUTIONS

WOOD PRESSURE-TREATED WITH WATERBORNE ARSENICAL PRESERVATIVES MAY BE USED INSIDE RESIDENCES AS LONG AS ALL SAWDUST AND CONSTRUCTION DEBRIS ARE CLEANED UP AND DISPOSED OF AFTER CONSTRUCTION. DO NOT USE TREATED WOOD UNDER CIRCUMSTANCES WHERE THE PRESERVATIVE MAY BECOME A COMPONENT OF FOOD OR ANIMAL FEED. EXAMPLES OF SUCH SITES WOULD BE STRUCTURES OR CONTAINERS FOR STORING SILAGE OR FOOD. DO NOT USE TREATED WOOD FOR CUTTING-BOARDS OR COUNTERTOPS. ONLY TREATED-WOOD THAT IS VISIBLY CLEAN AND FREE OF SURFACE RESIDUE SHOULD BE USED FOR PATIOS, DECKS AND WALKWAYS. DO NOT USE TREATED WOOD FOR CONSTRUCTION OF THOSE PORTIONS OF BEEHIVES WHICH MAY COME INTO CONTACT WITH THE HONEY. TREATED WOOD SHOULD NOT BE USED WHERE IT MAY COME INTO DIRECT OR INDIRECT CONTACT WITH PUBLIC DRINKING WATER , EXCEPT FOR USES INVOLVING INCIDENTAL CONTACT SUCH AS DOCKS AND BRIDGES.

HANDLING PRECAUTIONS

DISPOSE OF TREATED WOOD BY ORDINARY TRASH COLLECTION OR BURIAL. TREATED WOOD SHOULD NOT BE BURNED IN OPEN FIRES OR IN STOVES, FIREPLACES, OR RESIDENTIAL BOILERS BECAUSE TOXIC CHEMICALS MAY BE PRODUCED AS PART OF THE SMOKE AND ASHES. TREATED WOOD FROM COMMERCIAL OR INDUSTRIAL USE (E.G., CONSTRUCTION SITES) MAY BE BURNED ONLY IN COMMERCIAL OR INDUSTRIAL INCINERATORS OR BOILERS IN ACCORDANCE WITH STATE AND FEDERAL REGULATIONS. AVOID FREQUENT OR PROLONGED INHALATION OF SAWDUST FROM TREATED WOOD. WHEN SAWING OR MACHINING TREATED WOOD, WEAR A DUST MASK. WHENEVER POSSIBLE, THESE OPERATIONS SHOULD BE PERFORMED OUTDOORS TO AVOID INDOOR ACCUMULATIONS OF AIRBORNE SAWDUST FROM TREATED WOOD. WHEN POWER-SAWING AND MACHINING, WEAR GOGGLES TO PROTECT EYES FROM FLYING PARTICLES. AFTER WORKING WITH THE WOOD, AND BEFORE EATING, DRINKING, AND USE OF TOBACCO PRODUCTS, WASH EXPOSED AREAS THOROUGHLY. IF PRESERVATIVES OR SAWDUST ACCUMULATE ON CLOTHES, LAUNDER BEFORE REUSE. WASH WORK CLOTHES SEPARATELY FROM OTHER HOUSEHOLD CLOTHING.

Northeastern Log Homes

© 1995 by NLH Inc.

NO.	REVISION	DATE	BY	CKD

WINDOWS	MODEL: STANDARD DETAILS 096
DRN: MG	CODES
CKD: SRP	
PROJECT NAME: INFORMATION COVER SHEET	
DATE: JAN. 1, 1995	PLAN NO: NE
SCALE	SHT. NO

SPILLER'S N92847I